



| SCHEDULE OF OPENINGS | | | | | |
|----------------------|-----------|--------|------|--------|---|
| TYPE | DIMENSION | | SILL | LINTEL | REMARKS |
| | WIDTH | HEIGHT | | | |
| D | 1200 | 2700 | — | 2700 | WOODEN. DOUBLE SHUTTER |
| W1 | 1200 | 1900 | 900 | 2100 | WOODEN. WINDOW OPENABLE (FLY PROOF MESH OPENABLE) |
| W2 | 1200 | 1150 | 1500 | 2100 | WOODEN. WINDOW OPENABLE (FLY PROOF MESH FIXED) |
| FG | 1200 | 1670 | 130 | 1800 | SINGLE FIXED GLAZING |

| FINISHING SCHEDULE: | | | |
|---------------------|-----------------|-------------|----------|
| ROOM NAME | FLOOR FINISH | WALL FINISH | CEILING |
| BASEMENT FLOOR | VITRIFIED TILES | EMULSION | EXISTING |
| GROUND FLOOR | EXISTING | EMULSION | EXISTING |

NOTE:

- 1.Damaged ventilator and windows to be changed.
- 2.Damaged sink & work table to be changed.
- 3.Existing cabinets/lockers to be removed in basement floor.
- 4.Reroute existing pipelines in lunch room corridor.
- 5.Flooring to be changed to tiles.
- 6.Water proofing for entire basement floor.

NOTE:

- 1.All Dimensions are in MM.
2. Dimensions should be Re-checked at site.
3. Work to figured Dimensions, Do not scale this drawing.
4. Discrepancies if any should be brought to the notice of the engineer.

REFERENCE:

| | |
|-----------------------------|--|
| PROPOSED SHOWN IN | |
| EXISTING SHOWN IN | |
| ALU.PARTITION SHOWN IN | |
| 4½" BRICK WALL UPTO CEILING | |
| DEMOLITION SHOWN IN | |
| PROPOSED FURNITURE SHOWN IN | |
| EXISTING FURNITURE SHOWN IN | |
| REMOVE & REFIX SHOWN IN | |

FOR TENDER PURPOSE ONLY

CHRISTIAN MEDICAL COLLEGE -VELLORE.

MODIFICATION OF NEURO OFFICE GROUND & BASEMENT FLOOR FOR RADIOLOGY IN CMC MAIN CAMPUS

| | | |
|-----------------------------------|----------------------|--|
| BASEMENT FLOOR PLAN-PROPOSED PLAN | | |
| DATE :29.01.2024 | DRG.NO:CMC/RAD/AR-01 | |
| DRAWN: JANE | CHECKED: DEVAKI | |