



SCHEDULE OF OPENINGS					
TYPE	DIMENSION		SILL	LINTEL	REMARKS
	WIDTH	HEIGHT			
D	1200	2700	—	2700	WOODEN. DOUBLE SHUTTER
W1	1200	1900	900	2100	WOODEN. WINDOW OPENABLE (FLY PROOF MESH OPENABLE)
W2	1200	1150	1500	2100	WOODEN. WINDOW OPENABLE (FLY PROOF MESH FIXED)
FG	1200	1670	130	1800	SINGLE FIXED GLAZING

FINISHING SCHEDULE:			
ROOM NAME	FLOOR FINISH	WALL FINISH	CEILING
BASEMENT FLOOR	VITRIFIED TILES	EMULSION	EXISTING
GROUND FLOOR	EXISTING	EMULSION	EXISTING

NOTE:

1. Damaged ventilator and windows to be changed.
2. Closet to be changed in ground floor toilet.
3. Water leak to be fixed in ground floor.
4. Existing furnitures in ground floor to be retained.

NOTE:

1. All Dimensions are in MM.
2. Dimensions should be Re-checked at site.
3. Work to figured Dimensions, Do not scale this drawing.
4. Discrepancies if any should be brought to the notice of the engineer.

REFERENCE:

PROPOSED SHOWN IN	
EXISTING SHOWN IN	
ALU.PARTITION SHOWN IN	
4½" BRICK WALL UPTO CEILING	
DEMOLITION SHOWN IN	
PROPOSED FURNITURE SHOWN IN	
EXISTING FURNITURE SHOWN IN	
REMOVE & REFIX SHOWN IN	

FOR TENDER PURPOSE ONLY

CHRISTIAN MEDICAL COLLEGE -VELLORE.

MODIFICATION OF NEURO OFFICE GROUND & BASEMENT FLOOR FOR RADIOLOGY IN CMC MAIN CAMPUS

GROUND FLOOR PLAN-PROPOSED PLAN		
DATE :29.01.2024	DRG.NO:CMC/RAD/AR-02	
DRAWN: JANE	CHECKED: DEVAKI	