

NAME OF THE WORK :PROVIDING FALSE CEILING IN GROUND FLOOR OF OPD BLOCK , AT CMC, TOWN CAMPUS.						
TENDER SCHEDULE						
Sl.No.	Quantity		Description of the work	Rate	Unit	Amount
1	50.00	M²	Labour charges for dismantling & removing of existing aluminium/ Gypsum partitions,alu. doors, alu.windows,alu. fixed glazing and alu./wooden false ceiling(Grid work with covering panel boards) complete set with all available accessories with out any damage and the usable items to be handed over to deptl.store and the unusable items handed over to disposal including required scaffolding,clearing the the same away from site as directed.		1M²	
2	10.00	M²	Labour charges for dismantling & removing of wooden panel board coverings from existing wall panels, partitions complete set with all available accessories with out any damage and the usable items to be handed over to deptl.store and the unusable items handed over to disposal including required scaffolding,clearing the the same away from site as directed.,		1M²	
3	1,400.00	M²	Providing & fixing "DAIKEN" gypsum board ceiling tiles 9mm thick with Aluminium foil laminated on one side and PVC sheet laminated on the other side with hot dipped galvanised steel grid work, surface chemically cleaned capping, PVC finished in backed polyster paint, main tees of size 33(H) x 24mm every 1.20m centre to centre, stiched cross tee at 0.60m centre to centre to form a grid of size 600x600mm & suspending the grid from roof using 3mm GI rod, 6mm nylon rawl plug & I bolt at every 1200 intervals, laying "DAIKEN" gypsum 155 ceiling tiles of size 600x600mm over the formed grid having fire rating of 60 minutes as per BS 479/23 of 1987, light reflection of 85% including cost of all materials,required scaffolding,laying to proper line and level ,fixing and finishing in all respects etc., complete		1M²	
4			Supplying and fixing in position of coverings to the existing openings/ open Ventilators and wherever necessary using with 50X32 mm sized wooden frame backed with12/18mm thick commercial plywood of approved make including cost of all materials, required screws and nails ,scaffolding ,painted with 1 coat of wood primer and 2 coats of synthetic enamel paint of approved make and colour ,fixing and finishing in all respects etc., complete.For Internal side			

Sl.No.	Quantity		Description of the work	Rate	Unit	Amount
a	50.00	M ²	50x32mm malasian vengai wooden scantlings for outer frame work,covering with 12mm thick commercial plywood of approved make		1M ²	
b	10.00	M ²	50x32mm malasian vengai wooden scantlings for outer frame work,covering with 18mm thick, commercial plywood of approved make		1M ²	
5	50.00	M ²	Supplying and fixing in position of existing wooden Ventilator closing only with 12mm thick,approved make of commercial ply wood wherever necessary (excluding wooden frame work), with necessary screws, nails & accessories etc., complete. (For Covering Ventilator closing)		1M ²	
6	15.00	M ²	Supplying and fixing in position of coverings to the existing openings/ open Ventilators and wherever necessary using with 50X32 mm sized wooden frame backed with12mm thick Bison board of approved make including cost of all materials, required screws and nails ,scaffolding ,painted with 1 coat of wood primer and 2 coats of synthetic enamel paint of approved make and colour ,fixing and finishing in all respects etc., complete.For External side		1M ²	
			Sub -Total			
			Add CGST 9%			
			Add SGST 9%			
			Total Amount			