

Name of the Work : Proposed Pulmonary Medicine Lab in 7th floor of "C" -block at CMC, Ranipet Campus						
SCHEDULE-B						
S.no	Qty	Unit	Description	Rate	Unit	Amount
1	900	Mtrs	Supply & wiring using 2 x 4.0 sq.mm PVC insulated (FRLS) copper wires along with 1 x 4.0 sq.mm. Green copper wire for continuous earthing in 25MM MS Conduit accessories(Concealed).		1RM	
2	100	Mtrs	Supply & wiring using 2 x 4.0 sq.mm PVC insulated (FRLS) copper wires along with 1 x 4.0 sq.mm. Green copper wire for continuous earthing in 25MM MS Conduit accessories(Open).		1RM	
3	250	Mtrs	Supply & wiring using 2 x 4.0 sq.mm PVC insulated (FRLS) copper wires along with 1 x 4.0 sq.mm. Green copper wire for continuous earthing in Existing 25MM MS/PVC Conduit accessories.		1RM	
4	75	Mtrs	supply & wiring using 2x2.5 PVC insulated (FRLS) copper wires along with 1x 2.5. Green copper wire for continuous earthing in 20MM MS Conduit accessories(Concealed).		1RM	
5	25	Mtrs	supply & wiring using 2x2.5 PVC insulated (FRLS) copper wires along with 1x 2.5. Green copper wire for continuous earthing in 20MM MS Conduit accessories(Open).		1RM	
6	20	Mtrs	supply & wiring using 2x2.5 PVC insulated (FRLS) copper wires along with 1x 2.5. Green copper wire for continuous earthing in Existing 20MM MS/PVC Conduit accessories.		1RM	
7	47	Nos	supply & fixing 6M Box with 2 No, 20A Socket outlet controlled by 2 No 20A, SP in an independent position(Concealed).		1No	
8	6	Nos	supply & fixing 6M Box with 2 No, 20A Socket outlet controlled by 2 No 20A, SP in an independent position(Open-in Dry Wall).		1No	
9	6	Nos	supply & fixing 6m Box with 2 No, 10A Socket outlet controlled by 2 No 10A, Switch(Concealed).		1No	
10	2	Nos	supply & fixing 6m Box with 2 No, 10A Socket outlet controlled by 2 No 10A, Switch(open-in Dry Wall).		1No	
11	150	Mtrs	Supply and wiring of 3 x 1.5 sq.mm FRLS PVC insulated copper wire in open MS conduit (Heavy) for excess length wiring.		1RM	
12	8	Nos	Labour Charges for fixing of 2 feet light fixture on the Work Table. <b>(Material will be supplied by department free of cost)</b>		1No	
13	27	Nos	Labour Charges for fixing fixing of 18W round light fixture on false ceiling. <b>(Material will be supplied by department free of cost)</b>		1No	
14	4	Nos	Labour Charges for fixing fixing of 4 Feet LED batten light fixture. <b>(Material will be supplied by department free of cost)</b>		1No	

S.no	Qty	Unit	Description	Rate	Unit	Amount
15	150	Mtrs	Supply and laying of 4C x 25 sq.mm Al. Ar. Cable on wall surface / existing tray with clamping as required.		1RM	
16	4	Nos	Supply and providing End termination with DC gland for 4C x 25 sq.mm Al. Ar. Cable.		1No	
17	70	Mtrs	Supply and laying of 4C x 16 sq.mm Al. Ar. Cable on wall surface / existing tray with clamping as required.		1RM	
18	2	Nos	Supply and providing End termination with DC gland for 4C x 16 sq.mm Al. Ar. Cable.		1No	
19	110	Mtrs	Supply and Laying of 10 SWG copper wire for earthing.		1RM	
20	2	Nos	Supply and Installation of 3 phase 8 way double door 7 segment MCB DB comprising the following : 1 No - 63A, 4 Pole MCB, 3 Nos - 63A, DP RCBO 30mA, 18 Nos 16A, SP MCB.		1No	
21	6	Nos	Supply and Wiring of 1.5 Sq.mm FRLSH wire for 1 no Fan/Light point controlled by 1no 10A SP Switch with in 4.5 mtrs with suitable size of MS Conduit.		1No	
			<b>Sub Total Amount in Rs. (Excl.GST)</b>			
			<b>c/o to Consolidated Summary</b>			